



ADDENDUM NO. 1

TO THE CONTRACT DOCUMENTS AND SPECIFICATIONS FOR SKINNER BUTTE LIGHTING IMPROVEMENTS PHASE III

JUNE 18, 2016

JOB #5092

BID NUMBER 15

TO ALL PLANHOLDERS:

The following changes shall amend and supplement the project bidding documents only to the extent specifically shown and noted. All other conditions shall remain the same.

Bidders shall incorporate the effects of these changes in the appropriate bid items included in this addendum and the total of these bid items then add in the appropriate place on the bid form.

CHANGES TO CALL FOR BIDS AND PROPOSAL:

BID CLOSING DATE:

(DELETE) June 20, 2018 – 2:00 PM

(ADD) June 26, 2018 – 2:00 PM

CHANGES TO BID SCHEDULE:

(DELETE) Original Bid Schedule with printed date of 6/4/2018

(ADD) Revised Bid Schedule with revision date of 06/15/2016

CHANGES TO SPECIAL PROVISIONS:

00120.15 Examination of Work Site and Solicitation Documents; Consideration of Conditions Encountered

(ADD) Photos of the existing electrical equipment inside the service room in the NW corner of Lamb Cottage, in addition to existing exterior junction boxes, may be found at the following website: <http://tinyurl.com/yaxedz4o>

Record Drawings of the Phase I Lighting Improvements, including electrical information for Lamb Cottage, are available for contractor reference on the City of Eugene Engineering bids project website (<https://www.eugene-or.gov/bids.aspx?bidID=653>) In addition a hardcopy of the plans is available for contractor review at the City Engineering offices, 99 East Broadway Suite 400, Eugene, Oregon. The plans are provided for reference only and do not contain any bid or contract information but may aid in consideration of electrical work involved for new circuits at Lamb Cottage.

00160.30 Agency-Furnished Materials

(ADD) The following construction materials will be furnished by the City of Eugene:

- Two Benches as noted on the Plans.

Bench type will be the same as that specified on the Plans for Contactor purchase. Un-assembled packaged equipment will be available for Contactor pick-up at the City of Eugene Parks and Open Space yard at 1820 Roosevelt Boulevard in Eugene. City staff will load the Contactor's vehicle. Transport, off-load, assembly, on-site placement and installation shall be the responsibility of the Contractor.

CHANGES TO PLAN SHEETS:

3 Construction Site Management Plan

(CLARIFY) A site-specific CSMP is not provided or required on this project. This project is covered under the Narrative CSMP 2018 provided by the City of Eugene Annual Erosion Prevention Permit, as attached in the bid book documents. All construction practices shall meet the outcome requirements of the permit and as provided under Section 00280 of the Specifications.

C-3 Construction Plan – Detail D

(REVISE) "Bench installed by Others" note to read "Bench furnished by City of Eugene, installed by Contractor"

C-6 Construction Plan

(ADD) Two (2) 16 ga. wires on Circuit 6 are to be used for future low-voltage dimming and shall be shielded wire to minimize interference from line voltage conductors. Connect wires to 0-10V dimmers at light fixtures and terminate wires at existing lighting control box in Lamb Cottage. Future dimming control is by Others.

(ADD) At northwest exterior corner of Lamb Cottage complete the following work to terminate proposed lighting circuit conduits:

- Remove and replace existing approx. 4x7' concrete pad to modify junction boxes per below.
- Remove existing black plastic junction box enclosing existing building electrical supply.
- Install new Type JB1 polymer concrete box over existing building electrical supply.
- Remove and salvage existing polymer concrete junction box and McCain vandal resistant insert and brackets. Furnish box, insert, and brackets to Project Inspector.
- Install new Type JB3 polymer concrete box in conjunction with new and existing conduits.
- Install new junction boxes per Standard Drawing TM472 and TM472(A).
- Protect and preserve existing electrical supply conductors and conduits.
- Work excludes new conduits from new junction box to or into building at this time. New conduits, as needed based on discussion and agreement with project electrician and Project Manager, will be considered Extra Work. Coordinate any new conduits to or into building prior to installation of new junction boxes.
- Junction box work shall be incidental to 'Electrical Supply – Connect to Existing'. New concrete will be paid for under 5.5" Concrete Surfacing unit price, inclusive of junction box areas.

D-2 Details

(REVISE) Light Fixture Schedule – Pole Type A2 (Poles 5-18)
Delete Zener Diode reference under Notes. Zener Diodes are not required.

D-4 Details – Variable Height Mow Curb and Bench Pad

(REVISE) “Bench installed by Others” notes to read “Bench furnished by City of Eugene, installed by Contractor”

If you have questions about this addendum or the project, please Adam Steffen at (541) 682-5040.

All bidders shall acknowledge the receipt of and acceptance of this Addendum No. 1 by signing and submitting the signed Addendum with the bid. Bids submitted without this Addendum, or with the Addendum not signed, will be considered informal.

ABS

Mark Schoening, P.E.
City Engineer

Receipt acknowledged and conditions agreed

this ____ day of _____, 2018.

Bidder: _____

By: _____

REVISED BID SCHEDULE

Project Number 5092	Project Name SKINNER BUTTE LIGHTING IMPROVEMENTS PHASE III
Bid Advertisement Date 6/6/2018	Inclusive through Addendum No. 1 Listed in Bold

Line No	Pay Item No.	Description	Quantity	Unit	Unit Value in \$ ¢	Extended Value in \$ ¢
1	2100010	MOBILIZATION	1.00	LS		
2	2900030	CWRR REPORT	1.00	EA		
3	2800170	CONCRETE WASHOUT FACILITY	1.00	LS		
4	2800010	EROSION CONTROL	1.00	LS		
5	2250010	TEMPORARY WORK ZONE TRAFFIC CONTROL, COMPLETE	1.00	LS		
6	1020060	ROOT ZONE EXCAVATION	16.00	HR		
7	3100099	REMOVAL OF SITE FURNISHINGS	1.00	LS		
8	9700080	ILLUMINATION COMPLETE	1.00	LS		
9	9700099	ELECTRICAL SUPPLY - NEW CABINET	1.00	LS		
10	9700098	ELECTRICAL SUPPLY - CONNECT TO EXISTING	1.00	LS		
11	9700097	RECONNECT EXISTING LIGHT CIRCUIT NEAR RIVERPLAY	1.00	LS		
12	7590099	5.5" CONCRETE SURFACING	1,842.00	SF		
13	7590098	5.5" CONCRETE SURFACING - TYPE 2 PAD	126.00	SF		
14	7590097	12" WIDE RAISED MOW CURB	29.00	FT		

REVISED BID SCHEDULE

Project Number 5092	Project Name SKINNER BUTTE LIGHTING IMPROVEMENTS PHASE III
Bid Advertisement Date 6/6/2018	Inclusive through Addendum No. 1 Listed in Bold

Line No	Pay Item No.	Description	Quantity	Unit	Unit Value in \$ ¢	Extended Value in \$ ¢
15	1065099	6' BENCH	4.00	EA		
16	1065097	6' BENCH INSTALL ONLY	2.00	EA		
17	1065098	TRASH RECEPTACLE	2.00	EA		
18	9050040	REMOVE AND REINSTALL EXISTING SIGNS	9.00	EA		
19	11200025	IRRIGATION REPAIR AND RELOCATION	10,000.00	FA	100	10,00000
20	10350097	TOPSOIL	1.00	LS		
21	10350098	LAWN SEEDING	1.00	LS		
22	10350099	BARK MULCH	1.00	LS		
TOTAL BID:						

NO CHANGES SHALL BE MADE TO THE PAY ITEM QUANTITIES CONTAINED HEREIN. ANY CORRECTIONS TO THE BIDDERS' ENTRIES SHALL BE MADE IN INK AND SHALL BE INITIALED BY THE BIDDER.